

**See attached documents for special issues and requirements.**

# Yavapai County Development Services

## Prescott Office

1120 Commerce Drive, Prescott, AZ 86303  
(928) 771-3214 Fax: (928) 771-3432



## Cottonwood Office

10 S. 6<sup>th</sup> Street, Cottonwood, AZ 86326  
(928) 639-8151 Fax: (928) 639-8153

Addressing – Building Safety – Customer Service & Permitting – Environmental – Land Use – Planning

---

## Construction Authorization for an Engineered Pad, R18-9-E309.4.09 General Permit: Less Than 3000 GPD Design Flow Alternative On-site Wastewater System

APN:402-04-276L

Date: February 15, 2018

Construction Authorization for the above-described facilities as represented in the approved plan documents on file with the Environmental Unit of the Yavapai County Development Services Department signed by Adam Goldenstein and dated February 15, 2018, is hereby given, subject to the following provisions:


- Construction shall be in accordance with plans and specifications stamped "CONSTRUCTION AUTHORIZATION (APPROVAL TO CONSTRUCT)," which are dated and signed by the authorized the Environmental Unit staff.
- Arizona Administrative Code Title 18, Chapter 9, Article 3. State Law (ARS 49-104, B.10) requires that the construction of the project must be in accordance with the rules and regulations of the Arizona Department of Environmental Quality.
- The wastewater treatment and disposal system shall be installed and constructed in strict conformance with the approved plans and specifications. SIGNIFICANT DEVIATION FROM THE APPROVED PLANS AND SPECIFICATIONS MAY RESULT IN WITHDRAWAL OF THE CONSTRUCTION AUTHORIZATION OR MAY REQUIRE MAJOR MODIFICATIONS TO THE SYSTEM TO MEET ADEQ AND YAVAPAI COUNTY STANDARDS. If changes from the approved plans and specifications are anticipated, the designer is urged to contact the Environmental Unit of the Yavapai County Development Services Department for possible approval of the changes or re-permitting of the disposal system.
- Approved system shall not serve more than the number of bedrooms or gallons per day noted on the first page of this permit.
- Effluent disposal area shall be located as per approved plans and contain the minimum disposal area as noted on the front page of this permit.
- Wastewater treatment plant effluent shall be contained within the owner's property line.
- The effluent disposal system shall be properly maintained and operated in accordance with ADEQ and Yavapai County policies.
- Systems designed by a non-registrant will be subject to construction inspections at key points of the installation as follows:
  - Components and geotextile material in place but not backfilled
  - Sand to the top of the Pad
  - Water tightness test
  - Final grade and drainage diversion
- Upon completion, the applicant shall submit three sets of signed, sealed and certified "as-built" plans for the system, the original Certificate of Completion (EEC), all testing data necessary for

system approval, and an Operation and Maintenance (O&M) Manual for the sewage disposal system. The certificate of completion and one set of “as-built” plans shall bear the original designer’s seal and signature. The “as-built” plans submitted by the designer shall ACCURATELY represent the installed treatment unit and disposal system location, components and configuration, and shall include all additional information necessary to issue a Discharge Authorization (Approval to Operate).

- The applicant shall ensure that the following tasks are performed, as applicable.
  - Components are installed on a firm foundation that supports the components and operating loads;
  - The site is prepared to protect native soil beneath the soil absorption area and in adjacent areas from compaction, prevent smeared absorption surfaces, minimize disturbances from grubbing, and otherwise preclude damage to the disposal area that would impair performance;
  - Components are protected from damage at the construction site and installed in conformance with the manufacturer's instructions if consistent with this Article;
  - Treatment media is placed to achieve uniform density, prevent differential settling, produce a level inlet surface unless otherwise specified, and avoid introduction of construction contaminants;
  - Backfill is placed to prevent damage to geotextile, liner materials, tanks, and other components;
  - Soil cover is shaped to shed rainfall away from the backfill areas and prevent ponding of runoff; and
  - Anti-buoyancy measures are implemented during construction if temporary saturated backfill conditions are anticipated during construction.
- Engineered Pad installation requirements
  - In addition to the applicable requirements in R18-9-A313(A) an applicant shall place sand media to obtain a uniform density of 1.3 to 1.4 grams per cubic centimeter.

If construction has not started within two years of the date of issue this certificate will be VOID and a new application and fees will be required.

## VICINITY MAP




## GENERAL NOTES

1. SYSTEM DESIGN AND INSTALLATION SHALL COMPLY WITH ARIZONA ADMINISTRATIVE CODE R18-9-A314 AND ELJEN GSF ARIZONA DESIGN & INSTALLATION MANUAL SEPTEMBER 2010, WWW.ELJEN.COM
2. HOMEOWNERS MANUAL AND RECOMMENDED MAINTENANCE AVAILABLE FROM [HTTP://WWW.ELJEN.COM/LITERATURE](http://www.eljen.com/literature)

## SITE PLAN NOTES

1. THERE IS NO PUBLIC SEWER WITHIN 400' OF THE PROPERTY.
2. THERE ARE NO WELLS WITHIN 100' OF THE SEPTIC.
3. WATER TO BE PROVIDED BY SHARED WELL LOCATED ON ADJACENT PARCEL 402-05-276Q.
4. THERE ARE NO WATER LINES WITHIN 10' OF THE SEPTIC.
5. ALL SETBACKS ARE MAINTAINED AS SPECIFIED IN TABLE OF R-18-9-A312c.
6. SETBACK LIMITATIONS CLOSER THAN 200' AS SPECIFIED IN ARE INDICATED ON SITE MAP R18-9-A312c
7. SURFACE LIMITING CONDITION IDENTIFIED IN R18-9-A310(C)(2): WASHES TO THE EAST AND SOUTH.
8. SUBSURFACE LIMITING CONDITION IDENTIFIED IN R18-9-A310(D)(2): 5-12' DEEP TEST HOLES.
9. CLEAN OUTS SHALL BE PROVIDED IN THE 4" SEWER SERVICE 2' FROM THE HOUSE AND WORKSHOP.
10. ALL EASEMENTS AND RIGHT OF WAYS ARE SHOWN ON SITE PLAN.
11. DRAINAGE FROM ROOFTOPS OF STRUCTURES SHALL BE DIVERTED FROM THE ABSORPTION AREA
12. TRENCHES SHALL BE COVERED WITH A MINIMUM OF 12" OF SOIL BACKFILL.
13. PROPERTY CORNERS ARE MARKED WITH STEAKS AND SURVEY TAPE BY A RECENT SURVEY.
14. ALL CC&R REQUIREMENTS ARE MET.



## General Notes

REV 1  
ADD MILESTONES  
EDITED LINE DIAGRAM  
ADD HYDRAULIC ANALYSIS  
CHANGE TANKS  
CHANGE DESIGN FLOW & TRENCH LENGTH  
REV 2  
BILL OF MATERIALS: EFFLUENT FILTER FOR SECOND TANK VS FIRST

No.	Revision/Issue	Date

SITE PLAN AND  
COMPONENT LOCATIONS

YCDS-EU

Construction Authorization  
(Approval To Construct)

Date: 2/15/18 By: Mubuh KS18

Permit No. P5201800370


SEPTIC PLANS FOR  
GOLDENSTEIN RESIDENCE  
10685 E ROCKY HILL RD  
DEWEY, AZ 86327

Drawn By  
ADAM GOLDSTEIN  
Date  
2/15/18  
Scale  
1"=60'

Sheet  
1 OF 3

GOLDENSTEIN RESIDENCE  
SITE PLAN  
SCALE 1"=60'





## SEPTIC COMPONENT KEYNOTES

- 2-WAY CLEANOUT
- GRAY WATER VALVE
- 4" SDR-35 OR SCHD-40\* SEWER PIPE
- 1500 / 750 GAL SINGLE COMPARTMENT SEPTIC TANKS\*\* MEETING ALL REQUIREMENTS OF R18-9-A314
- DISTRIBUTION BOX SET ON LEVELED MASONRY SURFACE
- ELJEN ENGINEERED PAD TRENCH PER TRENCH DRAWINGS
- INSPECTION PIPES
- 4" VENT PIPE AT END OF EACH TRENCH





\*SDR-35 "HIGH STRENGTH" PIPE SHALL BE USED WHEN PIPE IS GREATER THAN 2' BELOW GRADE.  
 \*\*POLYTANK SHOWN: SNYDER NEXGEN D2 1500 / 750 ONE COMPARTMENT TANK

DESIGN CALCS	
SAR (SITE INVESTIGATION)	0.4
DESIGN TSS/BOD	5/5
SARA (R18-9-A312.D.3)	0.885
DAILY DESIGN FLOW (GAL)	900
MIN DESIGN LIQ CAP (GAL)	2000
REQ. ABSORPTION AREA (FT^2)*	1016.6
B43 AREA PER EACH (FT^2)*	20
B43 UNITS NEEDED CALC.*	50.8
B43 UNITS USED	68
TRENCH LENGTH CALC. (FT)*	203.3
TRENCH LENGTH USED (FT)	280
SAND CS AREA (FT^2)	8.02
SAND VOLUME (FT^3)	2246
SAND DENSITY (LB/FT^3)	100
SAND (TON)	112

\*DESIGN CALCULATIONS BASED ON ELJEN GSF ARIZONA DESIGN & INSTALLATION MANUAL SEPTEMBER 2010, WWW.ELJEN.COM

TEST HOLES				
TH	DEPTH*	GRADE EL.*	BOTTOM EL.	NOTES
#1	12'	4909.0'	4897.0'	TH#1-8 SIMILAR BUT VARY TO ROCK REFUSAL. 0-1' TOPSOIL, 1-8' 70% ROCK WITH SCL IN MATRIX EVIDENCE OF MOTTLING PRESENT THROUGHOUT INDICATING SEASONAL SATURATION
#2	12'	4909.5'	4897.5'	
#3	9'	4907.5'	4898.5'	
#4	5'	4904.5'	4899.5'	
#5	6'	4903.5'	4897.5'	
#6	12'	4903.5'	4891.5'	
#7	12'	4890.0'	4878.0'	
#8	8'	4884.5'	4876.5'	


\*TEST HOLE DEPTH IS FROM ORIGINAL GRADE BEFORE FINAL GRADING.



General Notes		
REV 1		
ADD MILESTONES		
EDITED LINE DIAGRAM		
ADD HYDRAULIC ANALYSIS		
CHANGE TANKS		
CHANGE DESIGN FLOW & TRENCH LENGTH		
REV 2		
BILL OF MATERIALS: EFFLUENT FILTER FOR SECOND TANK VS FIRST		
No.	Revision/Issue	Date

SEPTIC PLANS FOR  
 GOLDENSTEIN RESIDENCE  
 10685 E ROCKY HILL RD  
 DEWEY, AZ 86327

Drawn By ADAM GOLDENSTEIN		Sheet 2 OF 3
Date 2/15/18		
Scale 1"=20'		



**HYDRAULIC ANALYSIS METHOD**

THE FOLLOWING HYDRAULIC ANALYSIS USED THE METHODOLOGY PRESENTED IN:  
"ON-SITE WASTEWATER TREATMENT PROCEEDINGS OF THE NINTH NATIONAL SYMPOSIUM ON INDIVIDUAL AND SMALL COMMUNITY SEWAGE SYSTEMS"  
MARCH 11-14, 2001, EDITED BY: KAREN MANCL, PUBLISHED BY: AMERICAN SOCIETY OF AGRICULTURAL ENGINEERS 2950 NILES ROAD, ST JOSEPH, MICHIGAN 49085-8659 USA

**SITE SOIL CHARACTERISTICS**

TEXTURE: SCL, STRUCTURE: BK, GRADE: 2, BOD<30 MG/L, SLOPE: 6-9%, INFILTRATION DISTANCE: 24-48"

ACCORDING TO TABLE 1 OF REFERENCED MATERIAL: INFILTRATION LOADING RATE: 0.6 GAL/DAY/FT<sup>2</sup> AND HYDRAULIC LINEAR LOADING RATE: 3.3 GAL/DAY/FT

**TRENCH LENGTH**

DIVIDE WASTEWATER VOLUME (900GPD) BY THE HYDRAULIC LINEAR LOADING RATE (3.3 GPD/FT) TO OBTAIN THE LENGTH OF THE DISPERSAL TRENCH:  
900GPD / 3.3 GPD/FT<sup>2</sup> = 272.7FT

**TRENCH WIDTH**

DIVIDE WASTEWATER HYDRAULIC LINEAR LOADING RATE (3.3GAL/DAY/FT) BY THE INFILTRATION LOADING RATE (0.6GAL/DAY/FT<sup>2</sup>):  
3.3GAL/DAY/FT / 0.6GAL/DAY/FT<sup>2</sup> = 5.5FT


**CONCLUSION**

LIMITING TRENCH LENGTH OF HYDRAULIC ANALYSIS (272.7ft) < TRENCH LENGTH USED (280ft)  
LIMITING TRENCH WIDTH OF HYDRAULIC ANALYSIS (5.5ft) = TRENCH WIDTH USED (5.5ft)  
THEREFORE IT IS RECOMMENDED THE SITE CONDITIONS ARE SUFFICIENT TO SUPPORT THE PROPOSED DESIGN FOR RELIABLE OPERATION

HYDRAULIC ANALYSIS

LIST OF MATERIALS	
1 EA	1500 GAL SEPTIC TANK: SNYDER NEXGEN D2 SINGLE COMPARTMENT
1 EA	750 GAL SEPTIC TANK: SNYDER NEXGEN D2 SINGLE COMPARTMENT
1 EA	EFFLUENT FILTER FOR SECOND SEPTIC TANK
3 YD^3	PEA GRAVEL FOR SEPTIC BEDDING
83 YD^3	ASTM C33 WASHED CONCRETE SAND
252 FT	4" DISTRIBUTION PIPE SDR-35 OR SCHD-40*
272 FT	4" PERFORATED PIPE
1 EA	2-OUTLET DISTRIBUTION BOX WITH SEALS
1 EA	3-OUTLET DISTRIBUTION BOX WITH SEALS
68 EA	B43 ELJEN PAD UNITS WITH GEOTEXTILE COVER AND WIRE CLAMPS
4 EA	TYPAR SOCK AND TAPE
8 EA	4" PIPE CAPS
-- EA	4" PIPE SDR-35 OR SCHD-40* FITTINGS AND CLEANOUTS AS NEEDED
-- EA	PIPE CEMENT GLUE AS NEEDED

\*SDR-35 "HIGH STRENGTH" PIPE SHALL BE USED WHEN PIPE IS GREATER THAN 2' BELOW GRADE.



General Notes

REV 1  
ADD MILESTONES  
EDITED LINE DIAGRAM  
ADD HYDRAULIC ANALYSIS  
CHANGE TANKS  
CHANGE DESIGN FLOW & TRENCH LENGTH

REV 2  
BILL OF MATERIALS: EFFLUENT FILTER FOR SECOND TANK VS FIRST

No.	Revision/Issue	Date

HYDRAULIC ANALYSIS  
MATERIAL LIST  
INSPECTION MILESTONES

SEPTIC PLANS FOR  
GOLDENSTEIN RESIDENCE  
10685 E ROCKY HILL RD  
DEWEY, AZ 86327

Drawn By  
ADAM GOLDENSTEIN

Date  
2/15/18

Scale  
1"=30'

Sheet  
3 OF 3